



BHAKTA KAVI NARSINH MEHTA UNIVERSITY, JUNAGADH

[Gujarat Public Universities Act No. 15/2023]

Government Polytechnic Campus, Bhakta Kavi Narsinh Mehta University Road, Khadiya, Junagadh-362263
(Gujarat)

Ph: 0285-2681400 || www.bknmu.edu.in || itcell@bknmu.edu.in

તા. ૦૬/૧૦/૨૦૨૬

:: જાહેરાત ::

આથી જાહેરાત આપવામાં આવે છે કે, ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢના ન્યુ કેમ્પસ ખાતે આવેલ ઇલેક્ટ્રીક ઇન્ફ્રાસ્ટ્રક્ચર, કમ્પ્યુટર સિસ્ટમ તથા સર્વર રેક્સ (Server Racks) માટે કોપર કેમિકલ અર્થિંગ તથા તેને અનુસંગિક પટ્ટી/વાયર વાયરિંગની કામગીરી(અર્થિંગ-૧૩ નંગ ખાડો કરીને અર્થિંગ કામગીરી) કરવાની આવશ્યકતા હોય, તેમાં રસ ધરવતા ઈસમોને જાણ કરાવવામાં આવે છેકે આ અંગેના ભાવ Annexure-1 ની વિગતો ધ્યાને લઈ આપના ભાવ સીલબંધ કવરમાં રૂબરૂ /કુરિયર/પોસ્ટ મારફતે નીચે સહી કરનારશ્રી ના સરનામે તા.૧૨/૧૦/૨૦૨૬ સુધીમાં મળી જાય તે રીતે મોકલી આપવા વિનંતી છે.

જે આ જાહેરાત પ્રસિદ્ધ થયેથી દિન-૦૫ (પાંચ) માં જરૂરી વિગતો સાથે "ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, ખડિયા, જૂનાગઢ" ના સરનામે પહોંચતા કરવાના રહેશે. આ સાથે કરવાની થતી કામગીરીની વિગતો અને શરતો નીચે મુજબ છે.

સીનીયર એન્જીનીયર (સિવિલ)

ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

ક્રમાંક/બીકેએનએમયુ/બાંધકામ/૧૯૯/૨૦૨૬-૨૭

તા. ૦૬/૧૦/૨૦૨૬

નિયમો અને શરતો :

1. સંપૂર્ણ કામગીરી ટેન્ડરમાં દર્શાવેલ શરતો અને સ્પેસિફિકેશન મુજબ કરી આપવાની રહેશે.
2. સંપૂર્ણ કામગીરી યુનિવર્સિટીના સીનીયર એન્જીનીયરશ્રી (સિવિલ/ઇલેક્ટ્રીકલ) ના સુચના અને માર્ગદર્શન મુજબ કરવાની રહેશે.
3. કામગીરી પૂર્ણ કર્યા બાદ યુનિવર્સિટીના ટેકનીકલ અધિકારી પાસે ટેસ્ટિંગ કરાવવાનું રહેશે.
4. કામગીરી પૂર્ણ કર્યા બાદ સાઇટ પરના એક્ઝ્યુઅલ મેઝરમેન્ટ (પ્રત્યક્ષ માપણી) પ્રમાણે બીલની ગણતરી કરવામાં આવશે.
5. આપના દ્વારા બીલ રજૂ થયેલ થી ૦૧ (એક) માસમાં બીલની ખરાઈ કરી ચૂકવણું કરવામાં આવશે.
6. કામગીરી દરમિયાન જે મશીનરી, મટીરીયલ, સાધનો તથા લેબરની જરૂરિયાત રહેશે તે આપના દ્વારા કરવાની રહેશે.
7. ટેન્ડરમાં દર્શાવેલ આઇટમની ખરીદી ટેકનીકલ અધિકારી ની સુચના તેમજ ISI STANDARD NORMS મુજબ કરવાની રહેશે.

પ્રતિશ્રી,

1. લાગતા વળગતા તમામ ઈસમો તરફ.
2. અત્રેની કચેરીના નોટીસ બોર્ડ ઉપર બહોળી પ્રસિદ્ધી અર્થે
3. આઈ.ટી.સેલ., વેબસાઈટ ઉપર બહોળી પ્રસિદ્ધી અર્થે.



Annexure-1

SOR					
Name of Work : Chemical, Earthing for Electrical Equipments, Computer Systems&Server Racks At BKNMU New Campus					
SR NO.	UNIT	QTY	Pre.	TOTAL	
1	Supplying & erecting in earthpit of minimum bore dia. 225mm size approved make Safe Earthing Electrode consisting Pipe-in-Pipe Technology as per IS 3043-1987 made of corrosion free hot dipped G.I.Pipes having Outer pipe dia of 80 mm having 80-200 Micron galvanising, Inner pipe dia of 40 mm having 200-250 Micron galvanising, connection terminal dia of 14 mm with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for following type of applications with chamber and heavy duty cover (A)(approved make OEM has to submit test certificate including value of earth resistance of installation duly stamped and signed by agency and officer Incharge has to ensure the value of earthing resistane mentioned in test Certificate) & having back filling compound of (B) Inner chemical (CCM Compound)- Resistivity:- 0.2 ohm / meter testing as per IEC 62561-2017, Voltage drop:- < 1 volt at no load & dry form, Sulphar content:- <2%(C) Back fill Compound :- Earthing compound should be capable to retain moisture for long time Necessary test report must be submitted by Agency.				BORE +ERTHIG + COMPOUND BAG
	[C] For Electrical Installation covering Transformer Neutrals, Lightning arrester Earthing, A.C.Plant & Sensitive Computer System(like Automation, SCADA)i.e. independent Earthing located in other than normal soil i.e. Soft Rock, Marshy Soil etc.. -Length of Pipe : 3 Mtrs. -Back filling Compound :2 nos Bags of 25 Kg.	13.00	10489.00	136357.00	
2	Providing and erecting required size HOT deep Galvanised iron strip for earthing of H.T., OCB/ ACB/ Transformer LT panel board, Motors etc. using proper clamp.	1040	77.00	80080.00	GI STRIP



BHAKTA KAVI NARSINH MEHTA UNIVERSITY, JUNAGADH

[Gujarat Public Universities Act No. 15/2023]

Government Polytechnic Campus, Bhakta Kavi Narsinh Mehta University Road, Khadiya, Junagadh-362263 (Gujarat)

Ph: 0285-2681400 || www.bknmu.edu.in || itcell@bknmu.edu.in

3	providing and erecting Mains with ISI marked, 1.5kV grade electrolyte multi stranded, annealed copper conductor with heat resistant PVC insulated conforms to IS 694, IEC - 227 erected in existing pipe of following size (Specifically for control panel, relays, power switchgears, motor starters & control wiring) with required size of copper lugs, nuts and bolts if required.								WIRE 2.5 MM
	(c) One wire 2.50 sq. mm	Mtr.	1040	34.00	35360.00				
4	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner.								LUG
	(A) 1.5/ 2.5/4/6 Sq.mm	Ea.	260	06.00	1560.00				
5	Providing & erecting Switch board for Computer or electric apparatus consisting of following modular type accessories mounted with PVC / Metallic concealed/open box with single mounting base frame covered with textured/metallic /white front plate,modules erected with necessary connections as directed 1 no. 6A/16A universal plug-switch combined. 3 nos. 6A Switch 3 nos. 6A 5 pin Plug								15A PLUG-4 WITH BORD
	For Modular Type Accessories								
	Cat. III	Ea.	13	1122.00	14586.00				
6	Supplying & erecting FRLS-XLPE(IS:7098)(I)-88 ISI unarmoured copper cable 1.1 kV grade to be erected as directed of following size.								
	(E) 3 core 2.5 Sq. mm	Mtr.	910	170.00	154700.00				3 CORE 2.5 MM BORD
			SUB TOTAL		422643.00				
			GST		76075.74				
			TOTAL		498718.74				

SYSTEM MANAGER

IT CELL

BHAKTA KAVI NARSINH MEHTA UNIVERSITY

JUNAGADH

Senior Engineer (Civil)

Bhakta Kavi Narsinh Mehta University

Junagadh.